Received: 07/08/2008 Status: CANCELLED Effective Date: 07/31/2008

PSC No. 1 - WATER

COMPANY: LONG ISLAND WATER CORPORATION d/b/a
LONG ISLAND AMERICAN WATER

SUPERSEDING REVISION: 0

INITIAL EFFECTIVE DATE: JULY 31, 2008

GENERAL INFORMATION

B. Meter Location:

- .1 The Corporation will provide a meter or meters for each service pipe unless otherwise agreed. The initial installation of the meter or meters may be made by the customer's plumber.
- .2 Meters are to be set horizontal in an accessible location near the entrance of the service pipe to the premises.
- .3 At the option of the Corporation, it may be required that the meters shall be set in a pit not less than three (3) feet square (preferably of brick or concrete construction) near the property line.
- .4 Stops or valves of standard make are required immediately before and after each meter.
- .5 Lead must not be used to make connections between the Corporation stop and the meter.

C. <u>Building Taps:</u>

- .1 No person except authorized agents of the Corporation will be allowed to tap the mains or insert corporation stops therein or operate any Corporation-owned valves.
- .2 A Corporation stop and service pipe are required for each building facing a street.
- .2.1 Stores, flats, or apartments, if divided by filled walls, will be considered as separate buildings requiring a separate corporation stop and a separate service pipe for each.
- .2.2 If the walls are not filled, a corporation stop for each division will be permitted or one for the entire building optional with the applicant.

D. <u>Installation and Maintenance of Service Pipe:</u>

.1 The service pipe without the limits of any street, avenue, road or way that is for any highway purpose under the jurisdiction of the legislative body of any city, town, village, county or the State of New York, or other public place open to the

Issued by: William M. Varley, President, 733 Sunrise Highway, Lynbrook, NY