

PSC NO: 1 ELECTRICITY
COMPANY: VILLAGE OF WESTFIELD
INITIAL EFFECTIVE DATE: 6/22/16

LEAF: 26
REVISION: 0
SUPERSEDING REVISION:

SERVICE CLASSIFICATION NO.7 (cont.)

If an equipment manufacturer, vendor, or any other party desires, documentation indicating compliance as stated above may be submitted to the Department of Public Service Commission for listing under the "Certified Equipment" list on the Department's website (<http://www.dps.state.ny.us/distgen.htm>).

Certification information for equipment tested and certified to UL 1741 latest revision by a non-NRTL shall be provided by the manufacturer, or vendor to the contacts listed on the Public Service Commission's website (<http://www.dps.state.ny.us/distgen.htm>) for review before final approval and posting under the Public Service Commission's "Certified Equipment" list. Utilities are not responsible for reviewing and approving equipment tested and certified by a non-NRTL. If an equipment is UL 1741 latest revision certified by an NRTL and compliance documentation is submitted to the utility, the utility shall accept such equipment for interconnection in New York State. All equipment certified to UL 1741 latest revision by an NRTL shall be deemed 'certified equipment' even if it does not appear on the Department of Public Service Commission's website.

Utility grade relays need not be certified per the requirements of this section.

VERIFICATION TESTING

All interface equipment must include a verification test procedure as part of the documentation presented to the utility. Except for the case of small single-phase inverters as discussed later, the verification test must establish that the protection settings meet the SIR requirements. The verification testing may be site specific and is conducted periodically to assure continued acceptable performance.

Upon initial parallel operation of a generating system, or any time interface hardware or software is changed, the verification test must be performed. A qualified individual must perform verification testing in accordance with the manufacturer's published test procedure. Qualified individuals include professional engineers, factory-trained and certified technicians, and licensed electricians with experience in testing protective equipment. The utility reserves the right to witness verification testing or require written certification that the testing was successfully performed.

Verification testing shall be performed at least once every four years. All verification tests prescribed by the manufacturer shall be performed. If wires must be removed to perform certain tests, each wire and each terminal must be clearly and permanently marked. The generator-owner shall maintain verification test reports for inspection by the utility.

Issued by: Andrew Thompson Director of Public Works, 23 Elm Street, Westfield, NY 14787