Status: CANCELLED Received: 10/18/2013 Effective Date: 11/10/2013

Media Three Corporation, Inc. P.S.C. No. 3 – Access

Revision 0 Effective Date: 11/10/2013 Superseding Revision:

## **ACCESS SERVICE**

- 4. SWITCHED ACCESS SERVICE (Cont'd)
  - 4.5 Obligations of the Telephone Company (Cont'd)
    - 4.5.6 Design Blocking Probability (Cont'd)

The Telephone Company will perform routine measurement functions to assure that an adequate number of transmission paths are in service. The Telephone Company will recommend that additional capacity (i.e., busy hour minutes of capacity or trunks) be ordered by the customer when additional paths are required to reduce the measured blocking to the designed blocking level. For the capacity ordered, the design blocking objective is assumed to have been met if the routine measurements show that the measured blocking does not exceed the threshold listed in the following tables.

For transmission paths carrying only first routed traffic direct between (1) an end office and customer's premises or a collocated interconnection location without an alternate route, and for paths carrying only overflow traffic, the measured blocking thresholds are as follows:

Number of **Transmission Paths** Per Trunk Group

Measured Blocking Thresholds in the Time Consistent Busy Hour for the Number of Measurements Taken Between 8:00 a.m. and 11:00 p.m. Per Trunk Group

Leaf: 124

	15-20	11-14	7-10	3-6
	<u>Measurements</u>	Measurements	Measurements	<u>Measurements</u>
2	.070	.080	.090	.140
3	.050	.060	.070	.090
4	.050	.060	.070	.080
5-6	.040	.050	.060	.070
7 or mo	re .030	.035	.040	.060